



**Engineering progress  
Enhancing lives**

## **YWCA Toronto Elm Centre**

Community housing towers implement innovative thermally-activated slab radiant heating and cooling system.

[na.rehau.com/projects](http://na.rehau.com/projects)



**ABCON**  
UNDER CONTRACT TO  
TORONTO HYDRO  
FOR ENQUIRIES CALL  
416-778-1800

**DANGER**

**DANGER**

# YWCA Toronto Elm Centre project features innovative thermally activated slab design



Since opening its doors in 1873, YWCA Toronto has worked to improve the lives of women and girls. As part of this effort, the organization constructed Elm Centre, a 302-unit affordable and supportive permanent housing complex in the downtown Toronto core. Spanning an entire city block, the complex includes 5-, 10- and 17-story residential towers, a restaurant, boutique and other commercial space, and the new YWCA Toronto corporate offices.

Closely aligned with the City of Toronto's energy efficiency and energy consumption targets, the building complex features a multi-stage heat recovery system, and a geothermal water-to-water heat pump system integrated with an innovative thermally-activated slab radiant heating and cooling system.

The installation includes 236,000 ft (72,000 m) of 1/2 in. RAUPEX O<sub>2</sub> Barrier crosslinked polyethylene (PEXa) pipe embedded in the center of each of the suspended 8-in. concrete slabs through each level of the three residential towers.

The design also increases useable floor space in residential units and as a non forced-air system, radiant heating and cooling also minimizes the circulation of airborne particles such as dust and allergens to enhance the health of residence. With mechanical equipment located outside the suites overall building operation and maintenance costs are also significantly reduced.

The overall circuit/zone configuration of the system allows the ability for each suite to be individually controlled by thermostats integrated with the building automation system. A total of 110 5- to 12-circuit PRO-BALANCE manifolds were installed in the corridor on every other floor of each building allowing for precise flow balancing and control to each circuit.

While a radiant floor system can achieve up to 32 Btu/hr-ft<sup>2</sup> in the heating mode and 16 Btu/hr-ft<sup>2</sup> in the cooling mode, both under ideal conditions, a thermally activated slab, because of its bidirectional output, can achieve output in the range of 50 Btu/hr-ft<sup>2</sup> in the heating mode, and 30 Btu/hr-ft<sup>2</sup> in the cooling mode. Thermally activated slab designs are ideal in multi-level structures, where the same concrete slab can be activated for heating from the upper side, and cooling from the underside.

**The system, designed to deliver 3 million Btu/hr, is fed by a geothermal well field of 90 500-ft boreholes, and is estimated to reduce carbon emissions by 415 tons – or 45 percent – per year when compared with conventional mechanical systems.**

**Project:** YWCA Toronto Elm Centre, Burlington, Ontario

**Construction type:** Residential, mixed use, opened in 2011

**Project scope:** 212,000 ft<sup>2</sup> (20,000 m<sup>2</sup>); 236,000 ft (72,000 m) of RAUPEX pipe

**Mechanical/Electrical Engineer:** Lam and Associates

**Mechanical contractor:** Nekison Engineering and Contractors

**Supplier and Designer:** Klimatrol Environmental Systems, Ltd.

**Architect:** regional Architects with Hilditch Architects

**REHAU systems used:** Radiant heating and cooling, RAUPEX<sup>®</sup> pipe, compression-sleeve fitting system, PRO-BALANCE<sup>®</sup> manifolds

For updates to this publication, visit [na.rehau.com/resourcecenter](http://na.rehau.com/resourcecenter)

The information contained herein is believed to be reliable, but no representations, guarantees or warranties of any kind are made as to its accuracy, suitability for particular applications or the results to be obtained therefrom. Before using, the user will determine suitability of the information for user's intended use and shall assume all risk and liability in connection therewith.

© 2023 REHAU 855.922 06.2023